



## Quotation for Iver Heath Pavilion

### Customer Details

---

The Ivers Parish Council  
45b High Street  
Iver  
Buckinghamshire, England  
SL0 9ND

### Site Details

---

Iver Heath Pavilion  
Church Road  
Iver Heath  
Bucks  
SL0 0RF

### Quotation Details

---

**Quotation:** #QUO00493

**Prepared by:** Russell Small

**Job Number:**

**Ref Number:** Fire Alarm Upgrade/Survey

**Date:** 21/12/2020

### Description

---

New Fire Alarm System - Provide new fire alarm system to grade L3 using standard PH30 cable. Following our survey detection provided will be conventional, coverage to all rooms on and leading to escape route with the exception of wet rooms which will be provided with notification devices only. No interfaces deemed required, detection provided to the large loft space with cable passing through. Majority of cabling will be within loft space, low level devices will be contained in conduit, sounder beacons will be installed on the ceiling not the wall to reduce containment. Works will be issued with Design, install & Commission BAFE certificates of compliance, Nationwide will also offer maintenance BAFE certificate of compliance if maintained by Nationwide. BAFE is the accreditation used in the UK for competent fire alarm contractors.

Description	Quantity	Sell	VAT	Total (Ex VAT)
Labour	58h 0m	£40.00	20.00	£2,320.00

**Nationwide Fire & Security (UK) Ltd**

Unit 1-2, Causeway Rowley Regis West Midlands England B65 8AA  
+448456589102 office@nationwidefands.co.uk

			%	
4 Zone conventional panel, EN54 less batteries	1.00	£230.03	20.00 %	£230.03
YUASA SLA BATT 12V 2.1AH	2.00	£13.00	20.00 %	£26.00
Optical Smoke Detector	14.00	£18.43	20.00 %	£258.02
Fixed Heat Detector	1.00	£17.59	20.00 %	£17.59
Standard Detector Base	14.00	£4.96	20.00 %	£69.44
Detector Base With Diode	1.00	£5.08	20.00 %	£5.08
Sounder VAD-Red Base- Red Flash & IP65 Base	7.00	£86.36	20.00 %	£604.52
Sounder Red & Low Profile Base	5.00	£15.86	20.00 %	£79.30
AEI 2X1.50MM FIRETEC STD RED 2C&E 100M FP200 [AEI]	4.00	£102.00	20.00 %	£408.00
MT CR6WH CONDUIT HG 20MMX3M WHITE RG20WH	3.00	£2.14	20.00 %	£6.42
Gent Manual Call Point XENS-805	5.00	£14.17	20.00 %	£70.85
Hinged protective cover pack of 10 XENS-892	1.00	£30.83	20.00 %	£30.83
End of line XENEX-EOL-C	4.00	£7.08	20.00 %	£28.32
Zone Plan	1.00	£200.00	20.00 %	£200.00
BAFE Certification Design, Install & Commission	1.00	£0.00	20.00 %	£0.00
Fixings	1.00	£80.00	20.00 %	£80.00
Red fire panel Fuse Spur, distribution board switch & Cable	1.00	£320.00	20.00 %	£320.00

**Total Excluding VAT:** £4,754.40

**Nationwide Fire & Security (UK) Ltd**

Unit 1-2, Causeway Rowley Regis West Midlands England B65 8AA  
+448456589102 office@nationwidefands.co.uk

<b>VAT Amount:</b>	£950.88
<b>Total Including VAT:</b>	£5,705.28

---

**Exclusions**

Any required 240v single phase A.C 24 hour maintained power supplies complete with a functional earth terminated adjacent to the controller, power supply units and equipment as described in the Power Supplies section of this specification to be arranged by others. Any builders work, cutting away, redecorating or making good. The services of a Carpet Fitter. The removal of any stock, furniture or fixtures, which may hinder the execution of our works. Such electricity as may be required for the powering of tools, plant etc. Washing and toilet facilities. A reasonable level of lighting in all working areas. A safe means of access to, and within, all working areas.

All the equipment supplied remains the property of Nationwide fire & security (UK) limited until paid for in full. Balance to be strictly 30 days from invoice.